



**Plain Square Weave**




**Twilled Square Weave**

**Notes:**

**NOT TO SCALE, ENLARGED TO SHOW DETAIL**

Pattern: aac  
 Construction: Plain Square Weave or Twilled Square Weave  
 Materials: Various  
 Specification:  $a \times a$  mesh  $\times c$  wire dia  
 Mesh count:  
 a number of holes per linear inch across width of material  $\times$  a number of holes per linear inch along the length of the material  
 Wire dia.:  $c$  (can be imperial or metric)  
 Clear opening:  $1/a - c$   
 % open area:  $a^2 \times (1/a - c)^2 \times 100$

Part No. <b>aac</b>	
Material Various	
Drawn <b>BR</b>	Date 24-May-2023
Approved <b>MW</b>	Date 24-May-2023
Tolerances depend on material and source. Mill test report available on request.	



170 Mulock Avenue, Toronto, Ontario, M6N 3C8  
 Toll-free 888.769.5280 Toronto 416.769.5280  
 www.ferrierwire.com info@ferrierwire.com

DWG No. <b>AAC</b>	Rev
Sheet Scale: NTS	Sheet 1 OF 1